
The Neutrino Beamline for the MINOS experiment




APS 2006, Dallas, April 21-25, 2006

Mary Bishai (MINOS collaboration)

mbishai@bnl.gov



NuMI/MINOS Concept



Pretarget region




Target hall

Decay pipe

NuMI Specifications

NuMI Beamline specs:

- Up to 4×10^{13} 120 GeV/c protons every 1.9 secs
⇒ 0.4 MW average beam power




- Main injector can accept up to 6 booster batches/cycle. 5 to 6 batches sent to NuMI in a single turn extraction (10μ sec).
- Losses not to exceed 0.01 watt/meter = very stable beam

MINOS expt specs:

- Minimize re-absorption of secondary hadrons in target = narrow target \perp to beam ($w=6.4\text{mm}$) ⇒ round beam profile with RMS width $\sim 1\text{mm}$
- Beam position stability on target $\pm 0.25 \text{ mm}$ and angular stability $\sim 60\mu \text{ radians}$.



Target Region Components



6.4 x 15 mm² graphite segments.

1m long = 1.9 interaction lengths.

$\mathcal{O}(10)$ KW beam power at 1 mm
beam width.

Water cooled.



Horn 1







Horn 2

Parabolic
magnetic lens.

3T at 200 kA



NuMI Beam Spectrum




Move target w.r.t to Horn 1: -10cm (LE), -100cm (ME), -250cm (HE)


Beam is 92% ν_μ , 6.5% $\bar{\nu}_\mu$, 1.5% $\nu_e + \bar{\nu}_e$



Measuring the Beam Profile



- **Foil Secondary Emission Monitors**
 - Beam profile + halo measurement
 - Very low mass ($5 \mu\text{m}$ Ti)
 - Reduced Beam Heating problems
 - Ti signal lasts longer in the beam



- **Mechanical/Vacuum System**
 - "Bayonet"-style insertion is compact
 - Frame is never in the path of beam
 - Insertion accuracy/repeatability
 - Vacuum $\sim 10^{-9}$ Torr on 30 l/s ion pump

10 SEMS deployed along 360 m of beamline



Measuring the Beam Position

Characteristics of NuMI Beam Position Monitors:

- Software algorithm to search 400 μ sec to find the beam.
- NuMI bunches come in 6 batches from booster. Position is measured batch by batch.
- Linear over 15-20 mm. 50 μ m accuracy in pretarget.
- 11 vertical and 13 horizontal measurements over 360m.





Feedback from BPMs used to auto-steer the beam to target center




Muon and Hadron monitors

Parallel-plate ionization chambers are used to monitor hadron and muon content of secondary beam.



Beam monitoring/control

Automated beam steering using feedback from 10-H and 9-V BPMs every spill. Magnet trims adjusted as needed to keep beam trajectory stable.




Time-stamped spill-by-spill beam information available offline for MINOS.




Target Alignment with Beam

Use low intensity beam and scan across target:




Maximum P.H. when beam passes between target and graphite protection baffle.

In-situ verification of beamline alignment with target hall components.



Horizontal scan (mm)




Vertical scan (mm)




Beam Performance - Power

NuMI Beam Performance, January 2005-March 2006



Beam Performance - Stability



Beam width stable with RMS:

~ 1.1 mm horizontal



~ 1.25 mm vertical

Beam position at target stable


to ~ 0.1mm

≥ 99.5% of beam is on target


Horizontal Batch Position at Target, Sep '05



Beam Performance - Targeting



Shift in muon centroid position by ± 5 cm \Rightarrow beam shift by $\pm 60 \mu\text{rad}$.





Targeting stability to $< 60 \mu\text{rad}$ maintained over run period.



Near Det. Flux uncertainties

Absolute p -beam intensity is known to better than 2%.

Dominant non-had. model uncertainty is from modeling skin-depth effect in horns. Overall beam performance uncertainties are < 3% in region of maximum sensitivity



Performance uncertainties << hadro-production model



Conclusions

MILESTONES:

- Spill intensity of 3×10^{13} protons
- Average power of 270 kW maintained over ~ 1 hour
- Integrated 1×10^{20} protons-on-target in approx 6 mos.
- Automated operation fully commisioned = very stable beam with low losses

2006 Goals:

- Finish spare target and horns.
- Improved cycle time \Rightarrow expect 2×10^{20} P.O.T. in 2006
- Booster batch stacking commisioning \Rightarrow higher intensity in 2007+.

