

GLA2011







# Pyhäsalmi site study





# **LAGUNA**

## **Design Study**

### **Underground infrastructures and engineering**

**(EU, FP 7)**

**TASKS OF ROCKPLAN:**

**DELIVERABLE 2.1**

+ assisting in deliverable 2.8, 3.1...3.4

**LAGUNA @ PYHÄSALMI, FINLAND**



# Deliverable 2.1

Site study of all LAGUNA options at Pyhäsalmi

Total of 279 pages

Three main parts:

G


Glacier

M



Memphys

L


Lena



## Glacier in comparison





## Glacier in comparison





## Glacier in comparison

The world biggest (over 40 m) man-made underground caverns are:

<i>Site</i>	<i>Country</i>	<b><i>span</i></b>	<i>length</i>	<i>height</i>	<i>depth</i>	
<i>Glacier</i>		<b>75 m</b>	75 m	38 m	900 m	(planned)
Gjøvik Olympic Cavern Hall	Norway	<b>61 m</b>	91 m	25 m	40 m	
Tytyri Mine, chalk mine museum	Finland	<b>60 m</b>			110 m	
Salmisaari coal storage silos	Finland	<b>42 m</b>	42 m	65 m	50 m	
Leppävirta, cross country ski hall	Finland	<b>40 m</b>	100 m	10 m	15 m	
Super- Kamiokande, neutrino det.	Japan	<b>40 m</b>	40 m	55 m	1000 m	
Vihanti mine	Finland	<b>40 m</b>			180 m	

In Finland the size of the cavern is not at the upper limit of the rock mechanical stability.


So far no client has ever requested for bigger caverns.



# Location of Pyhäjärvi / Pyhäsalmi in Finland

63° 39' 31" N  
26° 02' 48" E



You are here now







# 3-D impression of Pyhäsalmi mine



- 1440 meters


## LAGUNA, purpose:

- 1) to study the feasibility of the considered experiments
- 2) to prepare a conceptual design of the required underground infrastructure
- 3) to deliver a report that allows the funding agencies to decide on the realization of the experiment and to select the site and the technology






## Clearance from nuclear plants to avoid reactor neutrino events





Distance for CERN's possible future long distance neutrino beam exp.



CENTRE FOR UNDERGROUND  
PHYSICS IN PYHÄSALMI MINE

$L=2300\text{ km}$



IU  
S

Institute of Underground  
Science in Boulby mine, UK

$L=1050\text{ km}$

**SUNLAB**

Polkowice-Sieroszowice,  
Poland

$L=950\text{ km}$



IFIN -HH  
Unirea Salt Mine



$L=1570\text{ km}$

$L=630\text{ km}$

$L=730\text{ km}$

$L=130\text{ km}$




**LSC**

Laboratorio Subterráneo  
de Canfranc, Spain



Laboratoire Souterrain  
de Modane, France



Umbria,  
Italy



# ROCK CONDITIONS


- Geological conditions
- Rock temperature
- Earthquakes
- Hydrological conditions



Lagvna




## Geology: stable (ancient) bedrock conditions






# Earthquake sensitivity conditions







# Lithological map of the Pyhäsalmi volcanic complex



Radon content (in ventilated underground areas) 20 Bq/m<sup>3</sup>

vibration accelerations at 500m:  
0,013 g (due to earthquakes)  
0,020g (due to blasting activities)

Mine area (surface)

Mine area (-1430m)

Lake Pyhäjärvi

Future LAGUNA laboratory  
(~500m west from the mine)

## Lithologies

	Pegmatite granite
	Diabase
	Feldspar porphyry
	Porphyritic granite
	Granite
	Gabbro/diorite
	Quartz diorite
	Granodiorite

	Mafic volcanics
	Intermediate volcanics
	Intermediate tuffite
	Felsic volcanics
	Felsic tuffite
	Skarn
	Volcanic conglomerate
	Amphibolite
	Altered intermediate volcanics
	Altered mafic volcanics

	Altered felsic volcanics
	Ore
	Mica gneiss

## Other symbols

	Fault
	Graphite schist
	Skarn intercalations
	Mafic dyke

0.5 0 0.5 Kilometers




## Temperature conditions of in-situ rock

$T=5^{\circ}\text{C}$

$T=16^{\circ}\text{C}$


$T=22^{\circ}\text{C}$



Average air temperatures at surface in Pyhäjärvi are:  $-9^{\circ}\text{C}$  (Jan) ...  $+16^{\circ}\text{C}$  (July).

# ROCK MECHANICS

- Rock Strength vs. Rock Stress
- Rock behavior
- Deformations
- Reinforcements needs





## Rock strength vs. rock stress (concept level)

Strength =:

- compressive strength from sample testing (i.e. intact rock strength) &
- geological strength conditions (e.g. GSI-value): influence of cracks (like types, density, directions, length, smoothness etc.), stratification, weak zones etc
- combined = rock mass strength

Stress =:


- In situ stress situation (level and direction): condition before excavation
- Excavation induced increasing of stress around cavern (mainly tangential stresses)
- combined = stress around cavern

To be analyzed:

- If rock mass strength > stress around cavern = elastic behavior => OK
- If not => failure (plastic behavior, spalling, creep etc.) => challenges!

## Rock strength vs. rock stress (Finland)

Cumulative probability



Peak Strength of Mafic and Felsic Volcanites (intact)  $\sigma_{ci} = 232 \text{ MPa}$


Geological Strength Index = 77

Rock mass strength  $\sigma_{cm} = 132 \text{ MPa}$

Note: Pegmatite dykes (intact)  $\sigma_{ci} = 110 \text{ MPa}$  to be avoided

measurements and stress failure observations confirms

Rock mass strength  $\sigma_{cm} = 132 \text{ MPa}$






## Rock strength at Pyhäsalmi mine (Finland)

*Uniaxial compressive strength of intact rock is 200-250 MPa (median 232 MPa) and is comparable to the strength of structural steels (e.g. S235 is 235 MPa)*




## GLACIER – Stress Induced Damage (Spalling)





## GLACIER – Stress Induced Damage (Spalling)



GLACIER				
	Depth (m)	Spalling ( $\sigma_1 - \sigma_3 \geq 132$ MPa)	Max $\sigma_1 - \sigma_3$ (MPa)	Spalling depth (m)
	300	No	46	-
	600	No	88	-
	<b>900</b>	No	130	-
	1200	(Yes)	164 (171)	(0,8 m)
	<b>1400</b>	Yes	191 (199)	0,3 m (1,4 m)
	1700	Yes	230 (241)	2,2 m (3 m)



- **Based on current rock mechanical information and from the point of view of rock spalling GLACIER can be excavated 1200 m below ground surface level as such (or up to 1400 m by using elliptical shape).**
- Max  $\sigma_1$ - $\sigma_3$  values are indicative and only meant to illustrate the largest values that strain element(s) located on the wall or ceiling (usually loads that have accumulated on a single small element or point)
- The bracketed values in the table are the largest values of the elements located on the floor (due to sharp edge)
- The spalling depths are suggestive and the arrows in the pictures just illustrate different spalling areas, not the exact locations of the given spalling depth
- Results in the sharp edges at the bottom of the excavation shapes are visualized just for comparison – results can be optimized with a rounded shape
- As presented all the shapes can be optimized from a rock mechanical point of view by using elliptical shapes relative to the in situ stresses (increases cross-sectional area considerably)




# Rock strength vs. rock stress (Finland)


In situ stress (before excavation)

Depth (m)	$\sigma_{H1}$ (MPa)	$\sigma_{H2}$ (MPa)	$\sigma_v$ (MPa)
900	52	33	26
1100	64	40	32
1400	81	51	41
2000	116	73	58


Major principal stress is horizontal and bearing to N-W (310° clockwise from N).



GLACIER results at -900m (up) & -1700m (down)



LENA results at -1450m (left)



## GLACIER – Reinforcement solution

Current solution (at -1440 m level main halls): 50 mm steel fibre reinforced shotcrete + 2,2 m long steel rebar bolts & steel mesh + cable bolts & 50 mm of shotcrete



### For GLACIER:

50 % Cable bolts 20 meters # 2,4 meters  
50 % Cable bolts 12 meters # 2,4 meters  
(combined #1,7 m)

6 m immediate bolts

150 mm shotcrete  
with steel mesh

Total of 4000 rock bolts (29 km) and  
11500 m<sup>2</sup> (1200 m<sup>3</sup>)  
shotcrete



# INFRASTRUCTURE AT SITE

- Shafts and access tunnels
- Rock disposal
- On surface infrastructure
- Necessary new infrastructure



Lagvna




## Present Infrastructure at site

### Main challenge:

*Not to disturb mine production*

### Finland

- Old main shaft (to -500m)
- Main shaft (violet)
- Inlet ventilation shaft (blue)
- Outlet ventilation shaft (orange)
- Decline / access tunnel (yellow)






# LAGUNA, External installation / on surface constructions

Primary infrastructure (primarily needed and therefore also part of Laguna costs)

railway connection	is present to the Mine area and is in good condition
railway yard	is present on the Mine area and perfectly suitable for Laguna needs (2 <sup>nd</sup> biggest of Finland)
road infrastructure	is present and in good shape (nearby is the main north south corridor "Road nr. 4" between Oulu and Helsinki)
harbor	situated in Kokkola only 160km away and is connected by rail with the site
electric infrastructure	is present at site (110 kV power supply) and sufficient also for Laguna purposes
water availability	Pyhäjärvi lake nearby with a capacity of 0.83 km <sup>3</sup> and the water quality is good
transmission station	the Mine has its own electricity supply, but it is needed to construct the power transmission station for construction and operation on the surface
pipe line	fully operating fuel dry line operative in the Mine between surface and -1400; similar solution of these facilities to be used
airfield	minor airfield is present at 10km distance (main airports located in Oulu and Jyväskylä at 170km distance)
parking space	present at the Mine area (large enough also to host trucks and other bigger vehicles)
offices / lunch room	present at site but in use for the Mine; new office to be built, that also has room for seminars and other conventions as Laguna starts operating

## LAGUNA infrastructure at site

### Finland



### Main purpose of the infrastructure

- **Sufficient** (to conduct the experiment)
- **Efficient** (cost & process effectiveness)
- **Safe** (during all phases)

### Main aspects of the infrastructure

- good excavation strategy
- efficient rock disposal
- no disturbance with hosting site
- sufficient fresh air inlet
- effective outlet of return air
- safety
- supply routes for construction
- storage of material
- quality control of material at the vicinity
- supply route (pipe lines) for liquids




# RESULTS

- PRINCIPLE LAYOUT
- COST ESTIMATES
- CONSTRUCTION TIME



# GLACIER at 2500 m.w.e.



Giant Liquid Argon Charge Imaging Experiment  
(artistic impression by ROCKPLAN)

- *yellow*                *new cavern for tank construction*
- *green*                *access tunnels and auxiliary rooms*
- *blue*                *new shafts*
- *grey*                *existing infrastructure at 900m*



## 7.10.2009



# GLACIER

ROCKPLAN



7.10.2009

MAJOR  
IN-SITU  
STRESS



# GLACIER

CROWN LEVEL



# GLACIER

ROCKPLAN


7.10.2009

MAJOR  
IN-SITU  
STRESS



# GLACIER


INVERT LEVEL



# GLACIER

ROCKPLAN

7.10.2009





# GLACIER, cost estimate

## Preparation costs

• General & rock mechanical design	2,5 M€	
• Development & consulting service	2,0 M€	
• Site investigations	2,5 M€	
<b>Total preparation costs:</b>		<b>7,0 M€</b>

## Excavation costs

### Excavation

• Main Detector Cavern	156'000 m <sup>3</sup>	5,6 M€
• New tunnels	92'000 m <sup>3</sup>	4,1 M€
• Shafts	13'000 m <sup>3</sup>	5,9 M€
• Auxiliary Caverns	15'000 m <sup>3</sup>	0,7 M€

### Excavation additional costs

• Ventilation, electricity, drainage during excavation	1,8 M€
• Bulk transport to the existing Mine	0,5 M€
• Miscellaneous	1,5 M€

<b>Total excavation</b>	<b>277'000 m<sup>3</sup></b>	<b>20,1 M€</b>
-------------------------	------------------------------	----------------


## Reinforcement costs

• Bolting, subtotal:	7,0 M€
• Shotcrete & wire mesh, subtotal:	10,6 M€
• Other (groundwater & radon ingress prevention measurements)	0,2 M€

<b>Total reinforcement:</b>	<b>17,8 M€</b>
-----------------------------	----------------

**Total underground infrastructure costs** **44,9 M€**

# GLACIER, time schedule






## Overview of costs (FINLAND)

Phase	GLACIER	MEMPHYS	LENA
Site preparation	45 M€	125 M€	75 M€
<i>Site investigation</i> <i>Design, development &amp; managing</i> <i>Excavation</i> <i>Reinforcements</i> <i>Additional (ventilation, bulk transport)</i>			
Laboratory construction *	400 M€	575 M€	275 M€
<i>Tank construction</i> <i>Auxiliary constructions</i> <i>Liquids + handling / cooling</i> <i>Sensors (photomultipliers)</i> <i>Data handling, electricity etc.</i>			
Total **	445 M€	700 M€	350 M€

\* to be analyzed more thoroughly

\*\* without unforeseen, without operation costs

## Construction time and cash flow (FINLAND )





# Further research needed

- Mine infrastructure upkeep costs if the mine ends production at 2018?
- Is the existing hall system at -650 level suitable to be utilized?
- Could the outlet shaft be replaced by a connection to the existing outlet system?
- Given the latest rock mechanical data, is the -900 level still optimum?
- What is the optimum method for Liquid Argon procurement and delivery?